

#### PHAP15-00019

**Date:** June 15, 2015

Application Type:Certificate of AppropriatenessProperty Owner:Robert and Amy O'Rourke

**Representative:** Karla Frausto

Legal Description: Being 7 Sunset Heights 56 To 59, City of El Paso, El Paso County,

Texas

Historic District: Sunset Heights

**Location:** 1100 Los Angeles Drive

Representative District: #8

**Existing Zoning:** R-4/H (Residential/Historic)

Year Built: 1904 Historic Status: Landmark

**Request:** Certificate of Appropriateness for the removal of existing kitchen

windows, modification of the window opening to accommodate a larger

window, and replacement with a tripartite window

 Application Filed:
 6/10/2015

 45 Day Expiration:
 7/25/2015



### **GENERAL INFORMATION:**

The applicant seeks approval for:

Certificate of Appropriateness for the removal of existing kitchen windows, modification of the window opening to accommodate a larger window, and replacement with a tripartite window

#### **STAFF RECOMMENDATION:**

The Historic Preservation Office recommends APPROVAL of the proposed scope of work based on the following recommendations:

The Design Guidelines for El Paso's Historic Districts, Sites, and Properties recommend the following:

- Doors and windows are considered important character-defining features because of significant detailing.
- Windows in secondary facades shall be reviewed on a case by case basis.
- Retain and preserve the pattern, arrangement, and dimensions of door and window openings on principal elevations. Often the placement of doors and windows is an indicator of a particular architectural style, and therefore contributes to the building's significance. Doors and windows for new construction and additions should be compatible in proportion, location, shape, pattern, size, and details to existing units.
- When repair is not feasible, door and window products will be reviewed on an individual basis using the following criteria:
  - a. Architectural and historical compatibility
  - b. Comparison to original profile
  - c. Level of significance of original doors and windows to the architectural style of the building.
  - d. Three dimensional exterior applied muntins that simulate or match the original muntins may be approved. Single dimension interior applied muntins are not appropriate.

The Secretary of the Interior's Standards for Rehabilitation recommend the following:


- New additions, exterior alterations, or related new construction shall not destroy
  historic materials that characterize the property. The new work shall be
  differentiated from the old and shall be compatible with the massing, size, scale,
  and architectural features to protect the historic integrity of the property and its
  environment.
- New additions and adjacent or related new construction will be undertaken in such a manner that, if removed in the future, the essential form and integrity of the historic property and its environment would be unimpaired.

## **AERIAL MAP**




## **PLANS AND ELEVATIONS**

# 1100 LOS ANGELES - Kitchen (Existing Windows)



#### 1100 LOS ANGELES - Klichan (Replacement Windows)





## **PROPOSED WINDOW**

BMC

1366 Lomaland Dr El Paso, TX 79997 Phone: (915) 598-5421

JELD WEN

QUOTE BY: ralph jenny SOLD TO: k-designs

QUOTE #: JRAL00557

SHIP TO:

PROJECT NAME: o'roarke REFERENCE:

PO#: Ship Via: Ground/Next Truck

i	SIZE INFO	BOOK CODE DESCRIPTION	NET UNIT PRICE	QTY	PRICE
Line-1		SCD2152			
Rough Openin	ng: 22 1/8 X 52 3/4	Frame Size: 21 3/8 X 52			
Viewed from Exterior. Scale: 1/2' = 1'		Siteline Clad Double Hung, Aurilast Pine, Concealed Jambliner Brilliant White Ederior, Natural Interior, Nati Fin (Standard), Color Match Metal DripCap, 6 9/16 Jamb, 4/4 Thick, Standard Double Hung, No Finger Plows, Tan Jambliner, Chestnut Bronze Hardware, US National-WDMA/ASTM, NG 35, Insulated Low-E 366 Annealed Glass, Neat, Preserve Film, Standard Spacer, High Atthude, Traditional Gir Bd, 7/8" Bead SDL w/Perm Wood Trad'l. Bead Int BAR, Brilliant White SDL, Light Bronze Shadow Bar, Colonial Top Lite(s) Only 2 Wide 2 High Top Better/Use Mesh Brilliant White Screen, GlassThick=0.698, Clear Opening:17.6w, 22.4h, 2.7 sf U-Factor: 0.32, SHGC: 0.18, VLT: 0.42, Energy Rating: 10.00, CPD: JBL-N-880-00894-00002			
		PEV 2015.3:1.1235/POV 6-251 (05/07/15) MW	\$548.24	2	\$1,096.48
Line-2 Rough Openir	ng: 42 1/8 X 52 3/4	SCDP4152 Frame Size : 41 3/8 X 52	45 152		44,030.10
Viewed from Exterior. Scale: 1/2" = 1"		Siteline Double Hung Product, Sash Back (Picture) Clad Fixed Auralast Pine, Brilliant White Exterior, Natural Interior, Nati Fin (Standard), Color Match Metal DripCap, 6 9/16 Jamb, 4/4 Thick, US National-WDMA/ASTM, PG 35, Insulated Low-E 366 Annealed Glass, Neat, Preserve Film, Standard Spacer, High Attitude, Traditional Gib Bd, GlassThick-0.698, U-Factor: 0.31, SHGC: 0.21, VLT: 0.49, Energy Rating: 13.00, CPD: JEL-N-883-00004-00001 PEY 2015.1.1215,909 6.251 (05/27)19 WW			
		Pine, Brillant White Exterior, Natural Interior, Nati Fin (Standard), Color Match Metal D 6 9/16 Jamb, 4/4 Thick, US National-WDMA/ASTM, PG 35, Insulated Low-E 366 Annealed Glass, Ne Spacer, High Attitude, Traditional Gir Bd, GlassThick=0.698, U-Factor: 0.31, SHGC: 0.21, VLT: 0.49, I JEL-883-00004-00001	ripCap, at, Preserve Film	n, Stand	lard

QQ-2.20.1.1576 cust-037028 Quote Date: 6/1/2015

Last ModRed: 6/1/2015

Page 1 of 2(Prices are subject to change.)

Drawings are for risual reference only and may not be to exact scale. All last Modified: 6/1/2015 orders are subject to review by JELD-WITN